

Net Zero Design & SHTN 02-01 Sustainable Design and Construction (SDaC) Guide

# NHS Assure Conference

NHSScotland Sustainable Design and Construction (SDaC) Guide: SHTN 02-01

- Building a sustainable path to Net Zero

## A Policy for NHS Scotland on the Climate Emergency and Sustainable Development - DL (2021) 38



#### Policy requirements:

- Net-zero by 2040 or earlier where possible
- Buildings must be heated from renewable sources by 2038 or earlier
- Reduce scope 3 emissions from following sources to net-zero:
  - energy transmission and distribution, having regard to national plans to decarbonise the UK's electricity supply by 2035
  - $\circ$  waste disposal
  - $\circ\,$  business travel, including grey fleet
  - $\circ$  Water consumption
  - $\circ$  Waste water treatment
  - Leased assets
- Undertake annual Climate Change Risk Assessment
- Assess and enhance building resilience

- Update sustainable procurement strategy annually, prioritising net-zero transition and circular economy practices – The Sustainable Duty
- Promote Community Wealth Building initiatives
- Meet 2025 waste targets:
  - Reduce domestic waste by 15% and ensure no more than 5% to landfill
  - $\circ$   $\,$  Reduce food waste by 33%  $\,$
  - Ensure at least 70% of domestic waste is recycled or composted
- Enhance biodiversity and quality of greenspace
- Incentivise more active and sustainable travel:
  - Remove petrol and diesel vehicles 2025
  - Decarbonise fleet by 2032





Health Facilities Scotland NHS National Services Scotland Scottish Health Technical Note 02-01 NHSScotland Sustainable Design and Construction Guide (SDaC)

#### How we deliver sustainably

- Single process, but allows project specific standards to meet local needs
- ✓ Stakeholder engagement & co-production
- ✓ Tools for collaboration & assessment





#### **Collaborative co-production workshops**

Evaluation Matrix			being	Circularity			Climate Change							
SCIM	RIBA Plan of Work		W1. Healthy Places - Total Wellbe	ing	ू अप्र2. Indoor environmental Qualit	Ŷ	CE1. Circular design and construct	ion	CC1. Operational emissions		CC2. Embodied carbon		CC3. Water consumption	
Strategic Assessment	0 Strategic Definition		Consider how a design that delivers healthy places and supports total wellbeing through the creation of quality, accessible and desirable spaces will support NHSScotland's value and sustainability strategic investment priorities.	1- Commenced	Consider how indeor environmental quality sustainability strategic investment sustainability strategic investment quality of Care, Health of Population and Value & Sustainability).	4 - Complete	Consider how circular economy principles will support NHSScotland's value and sustainability strategic investment priorities.	2 - Established	Consider how a building designed to achieve net zero operational GHG emissions will support NHSScotland's value and sustainability strategic investment priorities.	3 - Almost complete	Consider how a building that achieves significantly reduced levels of embodied of carbon will support NHSScotland's value and sustainability strategic investment priorities.	4 - Complete	Consider how a building that integrates a water efficiency strategy can support an overall reduction in the operational carbon rotoprint and will support NHSScotland's value and sustainability strategic investment priorities.	4 - Complete
Initial Agreement	1 Preparation and Briefing	d learning	Within the brief, commit to: - Promoting design that prioritises physical, social, mental, occupational and economic wellbeing of all users; - Delivering quality space through the adoption of the Place Standard, AEDET and NDAP	2 - Established	Within the brief, commit to: - Prioritising physical wellbeing of users by ensuring internal environments are designed to create healthy and comfortable spaces for all; - Detailed IEQ strategy with defined perf. parameters	NIA	Within the brief, commit to circular design and construction processes & circular procurement hierarchy - prevent I reduce! I dentify opportunities for intervention - refer to industry guides e.g. UKGBC circular economy or kief for construction clients	NA	Within the brief, commit to: Delivery of a net zero GHG emissions development; development; development; benchmark; min. design performance measures (as referenced within quidance document)	NIA	Within the brief, commit to: N A lower embodied carbon development; S Comprehensive embodied carbon reduction S antategy:& Adoption of consistent methodology for WLC analysis.	3 - Almost complete	Within the brief commit to: Adopting the water efficiency hierarchy for the development; - Water efficient components; - Monitoring and leak detection; - Responsible procurrent. EU water label scheme	NA
Early OBC Final Design Statement	2 Concept Design	owledge an	Design driven by user needs; clinical and functional - a clear connection between design and users; Holistic approach to wellbeing -identify performance parameters that support identified wellbeing outcomes: Enabling outcomes:	3 - Almost complete	Stakeholder engagement - Recognise and acknowledge feedback from key user groups: Detailed dynamic simulation model - early design enalysis, ensuring accuracy of data; IEQ - strategy and technical performance review.	4 - Complete	Inform project strategy with suitable metrics: - Design out waste and pollution / Responsible design, procurement and construction practices / Design for assembly, disassembly and recoverability. - Useful interaction project & analize design	4 - Complete	Initial and detailed passive design analysis: Consider healthcare operational process and the accuracy and availability of operational templates; Early detailed simulation modelling and results review workshop; Beview ontimeation and renewables	NZA	Options appraisal-refurb. or new build / site selection. Establish baseline reporting figure to guide design; Detailed carbon reduction strategy; Ensure accuracy and robustness of data; Ibrative WIC caresement - ontions	4 - Complete	Options appraisal for reducing consumption for building and landscaping: - Fessibility study for rainwater harvesting system: - Avoid the need for decicated irrigation that requires mains supply. - Effective strategy for waste water pollution	1- Commenced
Review (pre-option / site s	election / masterplan)	kne	Internal approval											
ОВС	3 Spatial Coordination	Direvious POI	Integrated approach: High-quality, ergonomic design and creation of space that support all appects of wellbeing: Space that encourages movement; Encouraging social relationships; Purposeful design; Inclusive and accessible design	4 - Complete	Monitoring and control strategy: - Inhalive systems to support user interaction: Responsive control strategy: - Remote monitoring and programming, review with Estates Management and client representatives.	4 - Complete	Supply chain engagement and viability testing: Review of circular product innovations; Review existing and new procurement routes carries as opposed to products). On-going reviews: Monitor design developments, conduct regular reviews, evaluate the overall immact.	4 - Complete	Performance review workshop: - Detailed Sinulation Model wilk/trough: Consider apprational assumptions, internal environmental conditions, performance outcomes & EU; - Detailed review of metering, programme & control; - CTH and Estates (FM strategy review.	4 - Complete	Carbon budgets, reportinig and updates - literative process. Life Cycle Assessment and Life Cycle Cost integration to infrom options appraisal. Continue to review and update during design development stages.	4 - Complete	Detailed review of water sub-metering provision, location, specification and operation. Full integration with BMS platform for ease of monitoring and reporting.	4 - Complete
Review (pre-planning)		l ylq	Internal approval											
FBC	4 Technical Design	oroach & ap	Final specifications: - Desirable and usable space; End users feedback and usable in the sting influences final specification details; Review management and maintenace requirements.	NA	Detailed dynamic simulation modelling - technical design update: IEQ performance parameters - review and update prior to construction work commencing: Management and maintenance - strategy review and draft BUG content.	4 - Complete	Update results of LCA, LCC and carbon budget: Communicate information with full project team and supply chains: Earlier moving to construction stage. Encourage circular supply chains: Inform procurement and tender documentation.	NA	Change control - Approve any changes before construction and agree change control strategy: Quality assurance - Phin for impection during construction stage (who, how and when?) Soft Landings review - Technical design 'reality checking'.	4 - Complete	Supply chain engagement - viability assessment: Inform tender / procurement documentation. Update carbon budgets at technical design stage and obtain LCA verification (final technical design).	4 - Complete	Specification of leak detection system: - Automated alert, programmable system; - Integration with BMS [for remote monitoring, programming and alerts].	1- Commenced
Review (pre-construction)		app	Internal approval											
Construction & Commissioning	5 Manufacturing and Construction	oft landings	Provision and purpose of design features and accessible and inclusive spaces to be included and communicated within building user guides.	4 - Complete	Quality assurance and pre-completion testing to be completed prior to handover <i>t</i> occupation: - Acousto pre-completion inspection and testing: - Internal environment - air quality results etc.	4 - Complete	Responsible construction practices: - Responsible procurement and resource management strategies: Agreed metrics and reporting schedule. Change control: - Management of issues, client approval required.	4 - Complete	Quality monitoring: -Quality assurance inspections & client reporting: -Programme of physical testing fabric integrity lair- quality. Building user guides - review and sign-off	NA	Carbon management and mitigation strategy implemented and impacts "monitored and reported during "construction; Quality assurance - Scheduled reviews and tender workbu reporting	4 - Complete	Quality assurance: Change control procedure in place requiring client sign-off.	4 - Complete
Project Monitoring & Evaluation	6 Handover	Adopt s	Aftercare strategy - part of soft landings approach: - Showcasing of total wellbeing features communicated to end users during handover and aftercare sessions.	NA	Aftercare strategy - part of soft landings approach: - Communication and promotion of internal environment quality aspects and associated benefits to end users during handover and aftercare sessions. - Seasonal commissioning inspections.	4 - Complete	Lessons learned and measuring success: - Workshop to review benefits of applying circular economies to project: - Lessons and learning captured in report.	4 - Complete	CTH strategy in action - review aftercare programme: PEPC - Net Zero Carbon 'as-built'; Client in receipt of multi-disciplinary model - BML, Detailed Simulation Modelling, Ito support asset management, maintenance, in-use, adaptationit.	4 - Complete	As-built' review and Final WLC assessment report; Carbon budget comparator exercise; Review and document lessons learned.	4 - Complete	Programming of leak detection systems - client? end user engagement as part of soft landings training and aftercare programme.	3 - Almost complete
Review (pre-occupation)			Internal approval											
Project Monitoring & Evaluation	7 Use		Extended PDE monitoring - Functional performance analysis: occupant consultation, use of space, qualitative data, positive user interactions. Data disclosure - Capture and share lessons.	4 - Complete	Extended POE - Functional performance analysis - qualifative and quantitative data: occupant consultation, internal environment monitoring: link with KSAR process. Data disclosure - Capture and share lessons.	4 - Complete	Extended PDE - Review of circular business models in operation, updated LCC and WLC operational models Data disclosure-knowledge share, support supply chain development	4 - Complete	FM contracts - performance based energy consumption and prioritising comfort & wellbeing: Extended POE - commence 3 year programme; Data disclosure - capture and share lessons.	4 - Complete	Extended PDE - WLC impacts monitored and reported during operation and at end of life: Data Disclosure - capture and share lessons.	4 - Complete	Extended PDE - consumption monitoring, maintenance and management; Data Disclosure - capture and share lessons.	4 - Complete
Review (in-use)			Internal approval											
Key:														
1 - Commenced 2 - Established	l								www.w.nss.nho	ssco	t/nublications	/<יוכ	tain	
3 - Almost com	plete								<u>vv vv vv.1133.1111</u>	5.500		545		



#### **Collaborative co-production workshops**

Evaluation Matrix			Wellbeing						
SCIM	RIBA Plan of Work		Ref.	호 W1. Healthy Places - Total Wellbeing			W2. Indoor environmental Quality		
Strategic Assessment	0 Strategic Definition		T.LW	Consider how a design that delivers healthy places and supports total wellbeing through the creation of quality, accessible and desirable spaces will support NHSScotland's value and sustainability strategic investment priorities.	1- Commenced	W2.1	Consider how indoor environmental quality will support NHSScotland's value and sustainability strategic investment priorities (Person Centred, Safe, Effective Quality of Care, Health of Population and Value & Sustainability).	4 - Complete	
Initial Agreement Initial Design Statement	1 Preparation and Briefing	ning	W1.2	Within the brief, commit to: - Promoting design that prioritises physical, social, mental, occupational and economic wellbeing of all users; - Delivering quality space through the adoption of the Place Standard, AEDET and NDAP.	2 - Established	W2.2	Within the brief, commit to: - Prioritising physical wellbeing of users by ensuring internal environments are designed to create healthy and comfortable spaces for all; - Detailed IEQ strategy with defined perf. parameters.	N/A	
arly OBC		lge and lear	W1.3	Design driven by user needs; clinical and functional - a clear connection between design and users; Holistic approach to wellbeing-identify performance parameters that support identified wellbeing outcomes; Creation of valuable internal and external spaces.	3 - Almost complete	W2.3	Stakeholder engagement - Recognise and acknowledge feedback from key user groups; Detailed dynamic simulation model - early design analysis, ensuring accuracy of data; IEQ - strategy and technical performance review.	4 - Complete	
Review (pre-option / site s	election / masterplan)	owled	Inte	rnal approval					
ОВС	3 Spatial Coordination	viou s POE kr	W1.4	Integrated approach: High-qaulity, ergonomic design and creation of spaces that support all aspects of wellbeing; Space that encourages movement; Encouraging social relationships; Purposeful design; Inclusive and accessible design.	4 - Complete	W2.4	Monitoring and control strategy: - Intuitive systems to support user interaction; - Responsive control strategy; - Remote monitoring and programming, review with Estates Management and client representatives.	4 - Complete	
Review (pre-planning)			Inte	rnal approval					
FBC	4 Technical Design	oproach & ap	W1.5	Final specifications: - Desirable and usable space: End users feedback and usability testing influences final specification details; Review management and maintenacne requirements.	N/A	W2.5	Detailed dynamic simulation modelling - technical design update; IEQ performance parameters - review and update prior to construction work commencing; Management and maintenance - strategy review and draft BUG content.	4 - Complete	
Review (pre-construction)		ding s ap	Inte	ernal approval					

- Consider how your project can support strategic aim
- Make a commitment
- Inform the brief / design
- Review and approval
- Process of optimisation
- Review and approval
- Detailed design evaluation
- Review and approval



## **Overarching theme: Optimisation**

## • Soft Landings Principles

- End user needs
- Narrow 'performance gap'
- Smooth transition from construction to operation
- ✓ POE Verified outcomes in use



NHS

SCOTLAND



#### Stakeholders: Roles, responsibilities, contributions

#### Internal

- Project Managers
  - Governance
- Sustainability and Environment Managers
  - Ownership and delivery
- Soft Landings Leads
  - Key delivery roles
- End user representation
  - User needs (clinical, estates, patients, support etc.)
- Energy and Estate Management
  - Delivery
- Asset and Facilities Managers
  - Delivery
- Capital Projects
  - Business Case
- NHS Assure
  - Governance, quality assurance

#### External

- A&DS
  - Delivery support
- Project team
  - Key delivery roles
- Specialist consultants
  - Specialist delivery roles
  - .... and others





The themes and corresponding issues included in the matrix are summarised below: Wellbeing

Issues under the wellbeing theme promote the design and operation of an estate that is considerate to and prioritises the wellbeing of users, through the creation of comfortable, inclusive and healthy places. These include:

#### W1: Healthy Places - Total wellbeing

Social, Physical, Mental, Occupational, Economic Wellbeing Place-making Quality of outdoor space

W2: Indoor environmental quality

Thermal comfort Indoor air quality Air pollutants Sound levels Light levels Functional space

Controls

#### Circularity

Issues under the circularity theme focus on establishing practices that support a more circular economy by aiming to eliminate waste and extract maximum value from resources. This includes:

#### CE1: Circular design and construction practices

Designing out waste and pollution Keeping products and materials in use Regenerating natural systems Circular procurement and supply chains

#### Climate change

Issues under the climate change theme seek to enable the delivery of a sustainable and resilient estate that effectively manages climate and ecological risk. These include:

CC1: Operational emissions

- CC2: Embodied carbon
- CC3: Water consumption
- CC4: Environmental security
- CC5: Active travel and sustainable transport

#### **Priority themes**

✓ Wellbeing

## ✓ Circularity

## ✓ Climate Change

Vellbeine optimise operational performance

Circularity



## Priority theme: Wellbeing

- **Healthy Places**
- ✓ Total wellbeing
- Place-making
- Quality of and connection to outdoor space



- Place-based approach, delivery of healthy places
- Consider and optimise total wellbeing
- Use of place-making tools (AEDET and The Place Standard) in addition to NDAP
- Apply Building With Nature principles
- Identify design performance parameters that support agreed wellbeing and quality outcomes
- Benefits of holistic design approach clearly communicated and demonstrated





## Priority theme: Wellbeing

Indoor Environmental Quality

- IEQ strategy promotes wellbeing of all users
- Intuitive control and effective response
- Mitigate and manage Pollutants



- Apply Soft Landings principles, identify and understand end user needs (functional, operational, management and maintenance), capture lessons and learning
- Identify aspects of design that closely link with physical wellbeing and inform an IEQ strategy
- Consider IEQ impact during option appraisal / site selection
- Establish a fully transparent monitoring, review and evaluation process





## Priority theme: Circularity

- Circular design and construction
- Design out waste and pollution
- Keeping products in use
- Regenerating natural systems

## Circular procurement

Responsible supply chains



- Adopt a circular procurement hierarchy approach, prioritising reuse / repurpose opportunities
- Develop a project specific circular economy strategy, requiring circular design and construction processes
- Design in layers, aiming to optimise durability, resilience and lifespan
- Agree metrics and establish a monitoring, review and evaluation process (e.g. considering volume of recycled content specified and future opportunity for reuse / repurpose / recycle)





NHS

SCOTLAND

## **NHSS Sustainable Design and Construction Guide**

#### **NHSScotland Carbon Footprint**

Source: Delivering a net zero NHS



## Priority theme: Climate Change

- Operational energy and emissions
- Net Zero strategy
- Zoning and metering strategy that supports end user needs
- Performance review workshops
- Quality Construction monitoring
- Soft landings principles



- Commit to net zero outcomes that support NHSS and National policy
- Identify an appropriate Operational Energy Target benchmark
- Adopt a responsible energy hierarchy approach
- Utilise detailed passive design analysis findings to inform early development
- Develop accurate operational templates and detailed simulation models
- Demonstrate a process of optimisation





## **Priority theme: Climate Change**

**Embodied Carbon** 

- ✓ Whole life carbon approach
- Embodied carbon to practical completion target
- Integrated Life Cycle Assessment and Life Cycle Costing analysis
- ✓ Whole life carbon objectives
  - ✓ Water consumption



- Approach:
  - Whole life carbon strategy
  - Resource hierarchy approach
  - Embodied carbon target
  - Whole life objectives
    - Water hierarchy monitoring, discharge and pollution, leak detection
    - Use Stage emissions eliminate harmful emissions from insulants, paints, refrigerants etc.
  - Life Cycle Assessment baseline
  - LCA and LCC integration, inform options appraisal





#### **Priority theme: Climate Change**

# Early stage decision making influences:

- Construction carbon footprint
- Operational carbon footprint
- End of life carbon footprint







## **Priority theme: Climate Change**

**Environmental Security** 

- Integrated, landscape-led approach
- Green Space Factor
- Pollution prevention and mitigation
- Integrating greenspace interventions
- Protecting and enhancing ecology



- Identify environmental security and green space priorities and opportunities
- Adopt an integrated, landscape-led approach
- Commit to targeting Green Space Factor
- Early appraisals to consider risk and opportunity
- Site optimisation and enhancement strategy
- Creation of multi-functional space that supports climate and wellbeing



## Priority theme: Climate Change

- Active Travel and Sustainable Transport
- Accessible and sustainable travel options
- Places for everyone
- Integrated design approach



- Prioritise active travel and more sustainable transport options in a safe, friendly and inclusive way
- Adopt sustainable travel hierarchy strategy
- Recognising the need for functionality, quality and resilience
- Early appraisals to consider challenges and opportunities, present and future
- Site optimisation and enhancement strategy





Document download:

<u>Sustainable Design and Construction (SDaC) Guide (SHTN 02-01)</u>
<u>National Services Scotland (nhs.scot)</u>



Thank you

leanne.hannah@armila-sustainability.com

## Marie Porteous Monklands Replacement Project SDaC





## SDAaC Governance

- Soft Landings Group.
- Links to other Corporate Working Groups.
- NHS Scotland Assure NDAP team.
- MEP Design Team.





Potential target score for BREEAM 2018 assessment – 57.2% (Very Good)

## **Business Objectives**

#### **NHS Scotland Assure**



- Improving person-centered services.
- Improving the safety of patient care.
- Improving clinical effectiveness and enhancing patient experience and clinical outcomes.
- Improving the quality of the physical environment.
- Providing flexible and adaptable facilities across the healthcare system.







## **Indoor Environmental Quality**

## • MEP Programme;

- 53 Workshops over 4 months with Stakeholders across the organisation, AE's, APs, RPA & others.
- Daylight Modelling & Solar Shading.
- Energy Modelling.
- TM52 Model.
- TM54 Model.



## NHS Lanarkshire – University Hospital Monklands

VE Modelling for OBC

#### Daylighting - Simulation Report v1

Consultant: Eirini Mouroutsou Approver: Colin Rees Senior Project Consultant Divisional Head of Consultancy (Global)

Friday, 20 May 2022



NHS Scotland Assure

## **Modern Methods of Construction**

## **Embodied Carbon**



Pre-Cast Concrete Lattice Planks – Including Topping

DfMA Element	PCC Lattice Slabs	
Man-Hours Per Unit - DfMA	9.9 Hours	
Man-Hours Per Units - Traditional	28.4 Hours	
Forecast Man-Hour Saving Per Unit	18.5 Hours (65%)	1
Number of Units	1,443 No	
Total Forecast Man-Hour Saving	26,695 Hours	TI
		加速加速
	CANAGE CONTRACTOR	



Benchmarking

NSD

Embodied Carbon Estimate kgCO <sub>2</sub> e/m <sup>2</sup>	Alder Hey	Dumfries Ward	Dumfries Technical Block	The Grange
Substructure	61	99	103	41
Superstructure	196	284	273	229
Total	257	383	376	270









## **Options & Build Ups**

#### **OPTION 10** PROFILED ALUMINIUM CLADDING (RAINSCREEN) WITH BLOCKWORK INNER LEAF, ENERGY CENTRE



#### 2 HIGH LEVEL BUDGET COST: TBA

GWP calculation includes for 3mm thick cold formed aluminium sheet. Assumed that sheet will be 2mm thick but allowance made for castellated profile.

Allowance of 2.2kg/m2 aluminium has been made for sub frame (helping hand brackets, rails) but needs to be verified.

Allowance for anodisation of aluminium has been included in calculation (8.3KgCO2e/m2).



#### GLOBAL WARMING (KgCO2e/m2) – RESOURCE TYPES





Note: Build-up will only achieve 0.16W/m2K (above target value of 0.15W/m2K) when maximum thickness of 250mm Rockwool Rainscreen Duo-slab is utilised as advised by Rockfon. Requirement for U-value to Energy Centre to be reviewed with Wallace Whittle.

#### **Glare Analysis**

- Room Types 2 and 3, within the courtyards, very unlikely to experience glare. •
- The more exposed rooms types 4 and 5, consider refining the patient bed position to help ٠ limit glare potential.
- Patient bed position 2 shows less potential of intolerable glare than bed position 1. •
- Enclave C5 has a higher glare risk compared to the remainder of Block C, due to its greater . exposure to direct sunlight.
- W, SE and NW elevations see higher risk for bed position 1. •
- W, S, SW and SE elevations are more sensitive for bed position 2. •
- W facade followed by SE experiences the greater potential for hours of glare. •
- Glare risk mostly during the second half of the day, especially in room types 4 and 5. •
- The majority of glare instances occur around 5pm. ٠
- The selection of suitable positions could result in saving 2-3 hours of potential glare. •





#### **DGP** – **Observations**

Patient position 1 experiences visual comfort compared to position 2.

**NHS Scotland Assure** 



**Position 1** DGP=36.07%



**Position 2** DGP=100%



June 21st 15h



IES

< 35%	Imperceptik
35 - 40%	Perceptibl
40 - 45%	Disturbing
> 45%	Intolerable

## Summary

- Stakeholder Engagement.
- Whole Team Approach;
  - MEP Programme.
  - Soft Landings.
  - NDAP.
- Review and Update.
- Repeat.









National Treatment Centre - Ayr

# **Scottish Health Technical Note 02-01**

NHSScotland Sustainable Design and Construction Guide (SDaC)

## <u>Themes</u>

- CC1 Operational Energy
- CC2 Embodied Carbon
- CE Circular Design and Construction
- W2 Indoor Environment Quality
- W1 Total Wellbeing

CC1



Net Zero – Operational Energy (NZ-OE)

UKGBC Framework Definition of NZC – Operational Energy (April 2019): When the amount of carbon emissions associated with the building's operational energy on an annual basis is zero or negative. A net zero carbon building is highly energy efficient and powered from on-site and/or off-site renewable energy sources, with any remaining carbon balance offset

The Standard extends this definition of NZ-OE to prioritise Zero Direct Greenhouse Gas Emissions from Heating (ZEH) within the NZ-OE requirement. (See ZEH definition in this Glossary of Terms.)



CC1

# **Embodied Carbon**

#### Net Zero Public Sector Building Standard Obj.2 Construction Embodied Carbon =

Product Stage (modules A1 - A3) +

Construction Process (modules A4 + A5)



#### Whole Life Carbon = Operational Carbon + Embodied Carbon



CC2



<u>Embodied Carbon (</u>A1 – A5)

A1 – A3 – Materials, transport and manufacturing

A4 - A5 - Transport and Construction

350kgCO2e/m2 pass to contractor



Operational Carbon (B6 & B7) Operational Emissions (B6) Operational Water (B7)

180kWh/m2/yr

¥.

**Embodied Carbon** (B1 – B5) Maintenance, repair and refrigerants

Reduce as much as possible / Carbon Offset



**Embodied Carbon** (C1 – C3) End of Life – Demolition, Transport, Waste Processing & disposal

Carbon Offset



C1 – C3 – on demolition

WLCN	LETI	RIBA 👾

Version 'A' - May 2021

CC2

Whole Life Carl	oon - Achieving	WLCN/LETI						
		Assess Separately						
Project Stage	Upfront Carbon (A1-A5)	In-Use Embodied Carbon (B1-B5)	In-Use Operational Carbon - Energy and Water. (B6-B7)	End of Life (C1-C4)	Module D			
Concept Design	Prediction based on generic values	Prediction based on generic values	Prediction based on generic values	Prediction based on generic values	Prediction based o generic values			
Detailed Design	Prediction based on specific values	Prediction based on specific values	Prediction based on specific values	Prediction based on specific values	Prediction based o specific values			
Practical Completion	Calculated on actual values	Prediction updated using as built values	Prediction updated using as built values	Prediction updated using as built values	Prediction updated using as built values			
Use Stage		Calculated on actual usage	Based on actual metered consumption	Prediction updated using as built values from B3-B5	Prediction updated using as built values from B3-B5			
End of life				Calculated on actual values	Prediction updated using as deconstructed values			
Future Projects (A1-A3)					Calculated on actual values			
Residual Offsets to achieve 'Net Zero'	At Practical Completion based on third party verified assessment	Annually in use based on third party verified assessment	Renewable energy with annual offsets for residual indirect emissions from energy and water	End of Life based on third party verified assessment	N/A			
KEY:								
Net Zero Carbon in design	n Designed to be 'Net Zero Carbon', but which does not have actual embodied or operational performance data to allow verification of 'Net Zero Carbon' status							
Net Zero Carbon enabled	Designed to be 'Net Zero Carbon' 'In-Use', but which does not have actual 'In-Use' or 'End of Life' performance data to allow verification of 'Net Zero Carbon' status							
Net Zero Carbon	/erified as 'Net Zero Carbon', using actual measured data and a third party verified assessment. Net Zero 'Upfront Carbon' can be claimed at Practical Completion, and 'Net Zero' 'In-Use' can be claimed annually.							

#### Material targets:

**Timber** – use from renewable sources of manufacturing – reclaimed

**Concrete** – 80% GGBS – addressing local opportunities

**Steel** – Maximise recycled content to 100% - or AEF processing if virgin material include shipping emissions from EU / abroad – powder coating

Insulation – natural materials addressing low carbon content – target less than 10kgCO2/m2 – identify recycled materials – refer to SEDA non-toxic construction materials guidance https://www.seda.uk.net/designguides - Toxic chemical reduction & Sustainable Renovation



- Building services F-Gas use to be GWP less than 1 – use TM65 for products where manufacturer data LCA is unavailable
- Plasterboard Compare fibre board and traditional plaster boards and alternative timber and recycled options. Options to be less than 1kGCO2/m2
- Flooring Address circular materials and hard finishes. Most flooring is glued and cannot be reused or recycled so alternatives should be addressed looking at finishes and recyclability – address environmental impacts and VOC's and toxic
- materials for wellbeing / health impacts **Re-use materials** should be
- stored ready for the build date – Reuse products should take highest priority including any site won materials – preference give to EPD products – Health impacts to take concerns address all NON TOXIC material choices





#### **Toxic Materials**



- No formaldehyde board use chipboard resin, materials that off gas formaldehyde, no OBS, glues, furniture, insulation, floor and wall fittings, wall cabinets, MDF board, wood fibre sarking, particle board etc...
- Drastically reduce the use of PVC PVC free wiring addressing health, toxicity and carbon impacts – ex EcoPower / EnduroFlex etc...

 Products must address recyclability & reusability including recoverability, and evidence of responsible ethical sourcing has taken place.

W2

Align Life Cycle Cost Analysis and Life Cycle Analysis and account for both cost and carbon impacts

Future bill of materials plan should be written in respect and repair and replacement quantities of materials

Plan for reuse, recover and recycle for all materials

At construction bill of all materials should be in PDF, as excel / BIM digital data can be hard to read in 40 years time (try opening an excel 2000 file now! horrible) New! - Place Standard with a Climate Lens





- A tool for structured conversations about a place
- Includes physical & social elements of place
- Understanding assets & areas for improvement
- Aligning developments with our goals and aspirations

# How are we using the Place Standard?

- Place Standard Climate Lens
- Adaptation to healthcare facility & timescales
- Opportunity to repeat process





<u>**Purpose</u></u> : To gather views from relevant stakeholders about different dimensions of 'place' relating to the proposed NTC development, so that the development can maximise the beneficial impacts for health, local communities, and the environment</u>** 

 In advance participants were provided with agenda, virtual visit slide pack of maps and pictures, including current surroundings and buildings

<u>Who:</u> Attendees were made up of NHS (estates, capital, hotel services, allied health professionals, anaesthesia, surgical services, SA HSCP, SA planning colleges, community engagement, South Ayrshire council fleet/sustainability/parks/equality/ teams ; Ayrshire Roads Alliance, NatureScot.

- Scored on how it currently stands to give us a baseline and to identify areas for targeting through the design process this work will feed into our Design Statement
- Public workshops held end of October planned with wider user groups of the facilities and under represented groups in Ayrshire to complete initial objective 1 response – verified by a 3<sup>rd</sup> party – SFT?
- Place standard will allow us to be part of the wider master planning of this area working in closer proximity to the council, local builders, planning committee, community partners and social groups encouraging views from a wider audience which will help feed into the planning design stages and set benchmarks for this net zero build.



NHS Scotland Assure



## Q&A